


# Case Study



## De-silting works

**Client - North Midland Construction PLC**

**Project Length - 2 Months**

**Project Value - £190,000+**

**Project - Ashop Weir**

### Key Issues

Temporary diversion of the river was required to enable safe removal of the silt for personnel working on the project.

### Solution

Ebsford removed approximately 5000 tons of material from behind the Ashop diversion weir. In addition to the desilting, further works included the installation of over 1000 tons of riprap and 70m of 3m high gabion baskets, created with site sourced, screened material.